41. In submitting the tenders, the contractors should specify definite rates wherever possible for the various items of work noted in the schedule hereto appended; but if they prefer to submit a lump sum quotation, such quotation must be accompanied by a set of detailed drawings and specifications fully describing the nature and quantity of work quoted for.

SCHEDULE.

No.	Items of work	Per	Quantity
1	Earthwork excavation and carving	C. yd.	332
2	Excavating the existing earth ram and carting	"	776
3	Concrete in mortar	S. ft.	3,090
4	Size stone in mortar	"	11,509
5	Burnt stone slabs 6" thick 2 line dressed fine at top and face	"	5,316
6	Italian marble for steps including honing and polishing	C. ft.	597·20
7	Italian marble flooring with slab 1½" thick including border and polishing ...	Sq.	21 56
8	Italian marble stone work pedestals and parapet	C. ft.	2,3 0 66
9	Top cornice course	"	60·44
10	Intermediate course	"	63·18
11	Bottom course	"	116·18
	Canopy main structure.		
12	Pillars base	"	54·17
13	Tapering base	"	40·00
14	Straight portion	"	22·82
15	Cornice moulder	"	4·15
16	Base block	"	7·08
17	Shafts	"	36·97
18	Capitals	"	5·50
19	Top piece	"	4·58
20	Top capitals	"	16·50
21	Growing pieces	"	28·11
22	Brackets	"	238·96
23	The rectangular panelling of the boxing alround the girders	"	159·60
24	Interior cornice above beam	"	233·33
25	Do octogonal	"	129·82
26	Interior cornice sixteen sided course	"	40·88
27	Base of dome circular course	"	86·25
28	Do intermediate course	"	88·88
29	Do cornice top course	"	85·25
30	Blocking course over lovey	"	108·25
31	Intermediate slabs of pedestals of parapet	"	105·12
32	Coping slabs of pedestals of parapet	"	...
33	Corner finial over pedestals of parapet base portions	"	94·76
34	Intermediate finials over parapet	"	51·68
35	Ceiling slabs below lovey	"	99·75
36	Horizontal beam course below lovey	"	56·92
37	Pendants below lovey	"	21·75
38	Pendants below interior cornice	"	3·28
39	Interior ceiling dome	"	284·61
40	Small brackets at ends of beam below lovey	"	11·25
	Total ...		4,744·78
41	Italian marble slabs 1" thick over lovey	S. ft.	714·00
42	Italian marble flooring 1½" thick over cement concrete bed between parapet and Dome.	"	·87
43	Armoured cement concrete work	C. ft.	541·87
44	Shell lime plaster panelling below lovey with mouldings	Sq.	2·78
45	Teakwood work including fixing with counter sunk bolts	C. ft.	277
46	Wrought iron frame work including bolts, nuts, etc., completed, fitted up in position.	Cwt.	322
47	Copper dome and finials burned and fitted in position.—		
	(a) Cost of copper	Seer.	5,210
	(b) Cost of sickling and smoothing the above fit for gilding ...	"	5,210
	(c) Labour charges for preparing copper sheets to required shape ...	"	5,210
48	Brass screws with heads gilt for fixing copper sheets of dome	Lump	sum.
49	Bolting of veneered slabs including necessary boring tools	Lump	sum.
50	Removing the existing cam and stone dressed slabs of top and cornice and refitting the same with necessary alterations.	C. ft.	541·90
51	Dismantling and carting the old walls where necessary	"	588
52	Lion figures over pedestals	No.	8
53	Lamp posts with Electrical fittings...	"	8
54	Centering scaffolding and other incidental charges	Lump	sum.
55	Laying out the garden in the space between the parapet of steps ...	No.	4

S. H. LAKSHMINARASAPPA
Archl. Executive Engineer.

KRISHNARAJASAGARA WORKS.

Notice is hereby given that sealed tenders will be received up to 5 P. M. on the 16th May 1918, for the supply of the undermentioned articles for the use of North and South Banks of the Krishnarajasagara Works, from 1st June 1918 to 31st December 1918.

2. The approximate estimate of quantities is given against each item in the list.

3. Tenders should be submitted in the printed forms, which may be obtained from the undersigned's office, and it should be accompanied by a list, in the form given below, showing the rates for the different items tendered.

4. Each tender must be accompanied by a deposit of Rs. 500 as earnest money, and be superscribed "tender for the supply of explosives" in default of which the tender will be rejected. The earnest money of the unsuccessful tenderers will be refunded.

5. The final acceptance of any tender well rest with the Chief Engineer who does not bind himself to accept the lowest or any tender or assign any reason whatever for the rejection of any tender.

6. The name of the successful competitor whose tender has been accepted, will be pasted on the Notice Board of the undersigned's office and intimated to him in due course. No enquiries regarding the acceptance or rejection of a tender will receive attention.

7. The rate tender of each item shall include cost of delivery free on Rails at French Rocks, Madras and Southern Mahratta Railway and at Bélagula Station, Mysore State Railway.

8. Orders will be placed with the successful tenderer, as the articles are required and the supply of an order in full must be completed within three weeks on receipt of the order, failing which the unexecuted portion of the order will be cancelled, orders placed elsewhere and earnest money deposited by the successful competitor forfeited, as a penalty for the non-execution of the order in full.

9. In quoting rates for each item, the manufacturing company's name should be noted.

Approximate quantities of articles required.

No.	Particulars	Unit	Quantity	Remarks
1	Dynamite $\frac{7}{8}$" ...	lbs.	6,000	
2	Trible detonators ...	Number ...	15,000	
3	White double tape fuse coils ...	Number ...	2,000	
4	Common black fuse coils ...	Number ...	10,000	

FORM OF TENDER.

Name of article	Unit	Rate	Free on Rails at	
			French Rocks	Belagula

Notice is hereby given that sealed tenders will be received up to 5 P.M., on the 16th May 1918, for the supply of the undermentioned articles for the use of North and South Banks of the Krishnaraja Sagara Works, from 1st June 1918 to 31st December 1918.

2. The approximate estimate of quantities is given against each item in the list.

3. Tenders should be submitted in the printed forms, which may be obtained from the undersigned's Office, and it should be accompanied by a list, in the form given below, showing the rates for the different items tendered.

4. Each tender must be accompanied by a deposit of Rs. 500, as earnest money, and be superscribed "tender for the supply of cement" in default of which the tender will be rejected. The earnest money of the unsuccessful tenderers will be refunded.

5. The final acceptance of any tender will rest with the Chief Engineer who does not bind himself to accept the lowest or any tender or assign any reason whatever for the rejection of any tender.

6. The name of the successful competitor whose tender has been accepted, will be pasted on the Notice Board of the undersigned's Office and intimated to him in due course. No enquires regarding the acceptance or rejection of a tender will receive attention.

7. The rate tender of each item shall include cost of delivery free on Rails at French Rocks, Madras and Southern Mahratta Railway and at Belagula Station, Mysore State Railway.

8. Orders will be placed with the successful tenderer, as the articles are required and the supply of an order in full must be completed within three weeks on receipt of the order, failing which the unexecuted portion of the order will be cancelled, orders placed elsewhere

and earnest money deposited by the successful competitor forfeited, as a penalty for the non-execution of the order in full.

9. In quoting rates the brand should be noted.

Approximate quantities of articles required.

No.	Particulars	Unit	Quantity	Remarks
	Red cross cement Ganapathy brand gladiator. Castle brand kalni cement ...	Tons ...	100 ...	Of any of the brands noted.

FORM OF TENDER.

Name of article	Unit	Rate	Free on Rails at	
			French Rocks	Belagula

Notice is hereby given that sealed tenders will be received up to 5 P.M. on the 16th May 1918, for the supply of the undermentioned articles for the use of North and South Banks of the Krishnarajasagara Works, from 1st June 1918 to 31st December 1918.

2. Approximate estimate of quantities is given against each item in the list.

3. Tenders should be submitted in the printed forms, which may be obtained from the undersigned's office, and it should be accompanied by a list, in the form given below, showing the rates for the different items tendered.

4. Each tender must be accompanied by a deposit of Rs. 500 as earnest money, and be superscribed "tender for the supply of stock and tools and plant" in default of which the tender will be rejected. The earnest money of the unsuccessful tenderers will be refunded.

5. The final acceptance of any tender will rest with the Chief Engineer who does not bind himself to accept the lowest or any tender or assign any reason whatever for the rejection of any tender.

6. The name of the successful competitor whose tender has been accepted, will be pasted on the notice board of the undersigned's office and intimated to him in due course. No enquiries regarding the acceptances or rejection of a tender will receive attention.

7. The rate tender of each item shall include cost of delivery free on rails at French Rocks, Madras and Southern Mahratta Railway and at Belagula Station, Mysore State Railway.

8. Orders will be placed with the successful tenderer, as the articles are required and the supply of an order in full must be completed within three weeks on receipt of the order failing which the unexecuted portion of the order will be cancelled, orders placed elsewhere and earnest money deposited by the successful competitor forfeited, as a penaulty for the non-execution of the order in full.

9. In quoting rates for each item, make and the manufacturing company's name or other known marks should be noted.

Approximate quantities of articles required.

No.	Particulars	Unit	Quantity	Remarks

FORM OF TENDER.

Name of article	Unit	Rate	Free on rails at	
			French Rocks	Belagula

List of articles.

Name of article	Unit	Quantity	Remarks
Small stores.			
1. Hasps and staples	Each	100	
2. Hinges do 3" to 6" brass and iron	"	100	
3. Nails screws of sizes	Dozen	150	
4. Nails tacks	lbs.	25	
5. Nails wire	Cwt.	5	
6. Tower bolts	No.	50	
Cardage.			
Twine, gunny	Cwt.	2	
Miscellaneous.			
Asbestos sheet ⅛" thick	Cwt.	2	
Do metallic	"	2	
Bath brick	No.	20	
Bellow nails	lbs.	10	
Belt, dressing	Cwt.	2	
Belt, fasteners, ¼", 5/8" and ⅜"	Gross	10	
Belt, syrup	Gallons	4	
Belting belata 6"	Ft.	500	
Do 8"	"	500	
Do 12"	"	200	
Belting leather 3" and 4"	"	50	
Boiler composition	Gallans	2	
Boiler syrup algharli	"	2	
Braided silk cord	Oz.	4	
Brushes scratch	R. ft.	6	
Cardboard of sizes	No.	25	
Chalk	Cwt.	1	
Chimney spare of dietz junior lanterns	No.	100	
Dammer	lbs.	25	
Emery cloth	No.	100	
Emery powder	lbs.	50	
Fluxite or past for soldering tins	Tin	10	
Gresolvent	"	6	
Lamp cotton	lbs.	56	
Leather, hydraulic	"	56	
Packing asbestos 5/8" and ¾" thick	"	56	
Do diamond ¼", ½", ⅝" and ¾"	"	56	
Do hemp	"	56	
Paper, sand, course and fine	Dozen	6	
Powder, black lead	lbs.	12	
Revets iron of sizes	"	56	
Rosin	"	56	
Rubber grey insertions ⅛" thick	"	56	
Salmaniac or amonium chloride	"	56	
Soap bar	No.	25	
Soap monkey brand	"	25	
Soft solder or silver lead	lbs.	56	
Splind fishing line thread	R. ft.	1,000	
Tallow	Cwt.	6	
Tape, metallic spare 50'	No.	12	
Do 33'	"	12	
Do 25'	"	12	
Tar	Cwt.	2	
Washers, iron of sizes	"	6	
Waste cotton	"	12	
White metal	lbs.	56	
Wax	"	12	
Wick for dietz lantern	R. ft.	100	
Worsted wool	lbs.	28	
Flexible wire rope of 5 strands 1½" dia.	R. ft.	1,500	
Tools and Plant.			
Axes pick steel with chisel and pointed ends (miled steel 6½ lbs.)	Dozen	12	
Mamaties swan necked, miled steel 5 lbs.	"	24	
Galvanized buckets 15" heavy patern revited	"	24	
Augers of sizes ⅝"	"	1	
Do ¾"	"	1	
Do 1"	"	1	
But hammers 25 to 28 lbs.	"	6	
File of kinds 8"	"	2	
Do 12"	"	2	
Do 14"	"	2	
Trovels of sizes 9"	"	4	
Do 10"	"	4	
Crobars steel 1" to 1¼" diameter miners drill quality	Cwt.	10	
Masons square steel	Dozen	2	
Hack saw blade spare, well's patent unbreakable 12"	"	2	
Oil speeder spring action	No.	6	
Saw hand of sizes 2' to 4½"	"	6	
Dietz junior lanterns with chemneys complete	Dozen	4	
Survey and Mathematical instruments.			
Foot rule box wood 2 four fold	No. each	12	
Tape measuring metalic with case 50'	"	6	
Do do 33'	"	6	
Do do 25'	"	6	
Do steel do 100'	"	6	
Do do 50'	"	6	
Copper rods ⅜" dia.	Cwt.	10	
Scrape gum metal	"	10	
Steel and iron of sorts ¼", ⅓", ½", ¾", 1" and 2"	"	10 each	
Minors drill steel ⅞" hen marked	"	20	
Do 1" and 1½" hen marked	"	10	
Kolar steel 1½" dia.	"	10	
Bolts and nuts of sizes	"	50	
Spare nuts	"	25	

Notice is hereby given that sealed tenders will be received upto 5 P.M. on the 16th May 1918, for the supply of the undermentioned articles for the use of North and South Banks of the Krishnaraja Sagara Works, from 1st June 1918 to 31st December 1918.

2. The approximate estimate of quantities is given against each item in the list.

3. Tenders should be submitted in the printed forms, which may be obtained from the undersigned's Office, and it should he accompanied by a list, in the form given below, showing the rates for the different items tendered.

4. Each tender must be accompanied by a deposit of Rs. 50, as earnest money, and be superscribed "tender for the supply of petrol and kerosene oil" in default of which the tender will be rejected. The earnest money of the unsuccessful tenderers will be refunded.

5. The final acceptance of any tender will rest with the undersigned who does not bind himself to accept the lowest or any tender or assign any reason whatever for the rejection of any tender.

6. The name of the successful competitor whose tender has been accepted, will be pasted on the Notice Board of the undersigned's office and intimated to him in due course. No enquiries regarding the acceptances or rejuction of a tender will receive attention.

7. The rate tender of each item shall include cost of delivery free on Rails at French Rocks, Madras and Southern Mahratta Railway and at Belagula Station, Mysore State Railway.

8. Orders will be placed with the successful tenderer, as the articles are required and the supply of an order in full must be completed within three weeks on receipt of the order, failing which the unexecuted portion of the order will be cancelled, orders placed elsewhere and earnest money deposited by the successful competitor forfeited, as a penanlty for the non-execution of the ordér in full.

9. In quoting rates for each item, the trade mark and the manufacturing Company's name should be noted.

Approximate quantities of articles required.

No.	Particulars	Unit	Quantity	Remarks
	Shell petrol	Gallons ...	400	
	White kerosene oil	Tins ...	200	

FORM OF TENDER.

Name of article	Unit	Rate	Free on Rails at	
			French Rocks	Belagula

Notice is hereby given that sealed tenders will be received up to 5 P.M., on the 16th May 1918, for the supply of the undermentioned articles for the use of North and South Banks of the Krishnaraja Sagara works, from 1st June 1918 to 31st December 1918.

2. The approximate estimate of quantities is given against each item in the list.

3. Tenders should be submitted in the printed forms, which may be obtained from the undersigned's office, and it should be accompained by a list, in the form given below, showing the rates for the different items tendered.

4. Each tender must be accompanied by a deposit of Rs. 200, as earnest money, and be superscribed "tender for the supply of articles for manufacturing gun powder" in default of which the tender will be rejected. The earnest money of the unsuccessful tenderers will be refunded.

5. The final acceptance of any tender will rest with the Chief Engineer who does not bind himself to accept the lowest or any tender or assign any reason whatever for the rejection of any tender.

6. The name of the successful competitor whose tender has been accepted, will be pasted on the notice board of the undersigned's Office and intimated to him in due course. No enquiries regarding the acceptance or rejection of a tender will receive attention.

7. The rate tender of each item shall include cost of delivery free on Rails at French Rocks, Madras and Southern Mahratta Railway and at Belagula Station, Mysore State Railway.

8. Orders will be placed with the successful tenderer, as the articles are required and the supply of an order in full must be completed within three weeks on receipt of the order, failing which the unexecuted portion of the order will be cancelled, orders placed elsewhere and earnest money deposited by the successful competitor forfeited, as a penalty for the non-execution of the order in full.

9. In quoting rates for each item, samples should be marked and sent.

Approxmiate quantities of articles required.

No.	Particulars	Unit	Quantity	Remarks
1	Salt petre	Tons ...	9	
2	Sulphur	Do ...	1	

FORM OF TENDER.

Name of article	Unit	Rate	Free on Rails at	
			French Rocks	Belagula

B. B. GARUDACHARYA,
Superintending Engineer.

WATER-SUPPLY DIVISION.

Notification dated 29th March 1918.

Notice is hereby given that separate sealed tenders will be received up to 12 noon of 1st May 1918, for the supply of uniforms, etc., to the different Pumping Stations attached to this Division for the year 1918-19. The probable number of uniforms, etc., required for each Pumping Station is noted in the separate statement appended. These quantities are not guaranteed.

2. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer's Office. The tenders should be accompanied by a statement showing the rates at which different articles will be supplied as per statement attached together with samples of the articles tendered for and labelled with the name of the tenderer.

3. The tender for each pumping station should be accompanied by a deposit of Rs. 50, in each case in cash or in Government Currency Notes as earnest money and be superscribed as "Tender for the supply of uniforms to pumping station" for the year 1918-19, in default of which tenders will be rejected.

4. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or assign any reason whatsoever for the rejection of any tender.

5. Within a week of the acceptance of any tender, the successful competitor will be required to execute the usual contract bond, one of the conditions being that the supply will be completely delivered by 1st July 1918, in default of which his tender will be considered cancelled and his earnest money forfeited.

6. The name of the successful competitor will be posted on the Notice Board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of any tender will receive attention.

7. The samples will be seen by the Executive Engineer in his office between 1 to 5 P. M. on office days. The uniforms should be complete with buttons, etc., in every respect and the cut and stitching should be up to date. The uniforms should be delivered at the respective pumping stations. Each station's supply should be brought to the Executive Engineer at his office for inspection and approval before the articles are delivered at different stations. The quality should be the same as that of the samples shown and approved of. Should there be any difference in any of the prepared